

DEVONSHIRE PARK REVITALIZATION



ADDENDUM #2

The addendum forms part of the Tender Documents and amends the original drawings and specifications. Changes to the RFT Documents are effective immediately. This addendum **MUST** be submitted with your submission. Failure to include all pages of this addendum will be cause for rejection of your bid. If the tender has been submitted, the Bidder may return the signed Addendum to The Corporation of the Town of Iroquois Falls by email to submissions@iroquoisfalls.com prior to the closing time and date. Addenda sheet(s) must be signed by an authorized signing authority.

This addendum is being issued to extend the official closing date and time, update the proposed schedule, and to provide clarification as follows:

1. REVISED CLOSING DATE AND TIME

The official closing date and time of Tender 2026-RFT-REC-06 has been extended to: **Friday, July 17, 2026 at 2:00 p.m. EST.**

2. The timeline for completion has been adjusted as follows:

Weather dependent, installation of base playground and splash equipment to be completed by October 30, 2026, with completion of surfacing and finish landscape no later than May 30, 2027. Any modifications to the schedule must be submitted as part of the bid.

3. Section 7 General Specifications: 4.18 Cast-in-place Concrete, has been removed as follows:

18. ~~Moisture Retention:~~ The period for which moisture is applied or retained in the concrete surface shall be not less than seven (7) days immediately following the placing of the concrete.

DEVONSHIRE PARK REVITALIZATION

4. Section 7 General Specifications: 9.1.2 Supply and Installation of Manufactured Play Equipment, has been revised as follows:

2. Installation certification by a playground inspector certified to inspect play equipment and associated safety surfaces in the Province of Ontario, and submission of certification to the Town prior to substantial completion is required.

5. Section 7 General Specifications: 9.5 Supply and Installation of Manufactured Play Equipment, has been revised as follows:

5. **Footings:** direct embedment type in cast-in-place concrete. The play equipment supplier shall provide play equipment footing details that meet the needs of the play equipment and provide stability within the context of the site's soil and frost-depth conditions.

6. Section 7 General Specifications: 9.9.10 Supply and Installation of Manufactured Play Equipment, has been revised as follows:

10. **Steel Posts:** steel posts are manufactured from 5" O.D. tubing (min.) with a wall thickness of .120" (min.) and shall be galvanized after rolling and shall have both the I.D. and the cut ends sprayed with a corrosion resistant coating. Posts for Motion Model 197057 shall be sized as per manufacturer's specifications.

Steel Post Mechanical Properties:

- Yield Strength (min): 50,000 PSI
- Tensile Strength (min): 55,000 PSI
- Elongation: 25% in 2 inches
- Modulus of Elasticity: 29.5 x 10⁶ PS

DEVONSHIRE PARK REVITALIZATION

7. Section 7 General Specifications: Add Section 15.2 Supply and Installation of Manufactured Water Play Equipment, as follows:

2. No additional engineering is required for splashpad surfaces.

AUTHORIZED SIGNATURE

DATE